





LOCATION MAP



LEGEND



PROPERTY LINE
ADJACENT PROPERTY LINE
ROAD RIGHT-OF-WAY
EASEMENT LINE
OVERHEAD POWER LINE
IRON PIN FOUND w/ DESC.
IRON PIN SET (#5 REBAR)

CURVE TABLE						
CURVE	RADIUS	LENGTH	DELTA	TANGENT	CRD. BRG.	CHRD
C1	1035.02	40.58	2°14'48"	20.29	S69°05'55"W	40.58
C2	125.64	116.07	52°56'00"	62.55	S85°33'43"E	111.99
C3	15.00	21.88	83°34'10"	13.40	S17°13'24"E	19.99
C4	347.15	94.87	15°39'32"	47.73	N16°43'08"E	94.58
C5	347.15	25.51	4°12'35"	12.78	N08°47'28"E	25.50
C6	149.35	212.28	81°25'46"	128.53	S45°22'23"W	194.84

LINE TABLE		
LINE	LENGTH	BEARING
L1	15.30	S03°54'45"E




SURVEY NOTES

1. THIS PROPERTY IS LOCATED IN FLOOD ZONE "X" WITH NO BASE FLOOD ELEVATION AS INDICATED ON FLOOD INSURANCE RATE MAP COMMUNITY PANEL NO. 45015C0595D, DATED 10-16-2004.
2. THE BEARINGS SHOWN HEREON ARE MAGNETIC AND AS SUCH ARE SUBJECT TO LOCAL ATTRACTION.
3. THIS PLAT REPRESENTS A SURVEY BASED UPON THE LISTED REFERENCES ONLY, AND IS NOT THE RESULT OF A TITLE SEARCH.
4. AREA DETERMINED BY COORDINATE METHOD.


CERTIFICATION NOTE

I HEREBY STATE TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF THE SURVEY SHOWN HEREON WAS MADE IN ACCORDANCE WITH THE REQUIREMENTS OF THE MINIMUM STANDARDS MANUAL FOR THE PRACTICE OF LAND SURVEYING IN SOUTH CAROLINA, AND MEETS OR EXCEEDS THE REQUIREMENTS FOR A CLASS A SURVEY AS SPECIFIED THEREIN. ALSO THERE ARE NO ENCROACHMENTS, PROJECTIONS, OR SETBACKS AFFECTING THE PROPERTY OTHER THAN THOSE SHOWN ON THIS SURVEY. SURVEY PRECISION EXCEEDS 1/10,000.

Frank D. Baker, P.L.S.
162 Seven Farms Drive, Suite 220, Charleston, S.C. 29492



SUBDIVISION PLAT
A 1.998 ACRE TRACT OF LAND
LOCATED AT 111 SPRING HALL ROAD
INTO TRACT 3-4 CONTAINING 1.313 ACRES
AND LOT 5 CONTAINING 0.685 ACRES
OWNED BY SD COMPANY, LLC
SURVEYED AT THE REQUEST OF GERALD D. ALTHEN
LOCATED IN THE CITY OF GOOSE CREEK
BERKELEY COUNTY, SOUTH CAROLINA
DATE: MARCH 30, 2006 SCALE: 1"=50'



ARCADIS

ARCADIS G&M, INC.
162 Seven Farms Drive, Suite 220
Charleston, S.C. 29492
Tel 843.345.5990 Fax 843.375.5993